# Williamson



Factory-Packaged
4 Sizes
70,000 to 175,000 Btuh Input
Natural or Propane Gas



# Gas-Fired Condensing Cast Iron Boiler

- □ AFUE's above 91%
- Sealed combustion or direct exhaust venting
- PVC, polypropylene, or stainless steel venting
- Multiple pass heat exchanger
- □ Cast iron primary heat exchanger
- Stainless steel condensing secondary heat exchanger
- Control module with indicator lights
- Inferred heat program providing automatic adjustment of boiler water temperature to match demand
- Hot surface ignition system
- Insulated heavy-gauge steel jacket








# **RATINGS**

		AHRI Certified Ratings				Boiler
Model	Input MBH	Heating Capacity MBH (1)	Net Water Rating MBH (2)	AFUE % (1)	Vent Diameter Inches (3)	Water Content Gal.
GWC-070	70	65	57	91.9	3	3.8
GWC-105	105	97	84	91.2	3	4.7
GWC-140	140	130	113	91.4	3	6.0
GWC-175	175	161	140	91.0	3	6.9

#### Notes:

- (1) Based on standard test procedures prescribed by the United States Department of Energy.
- (2) Net AHRI ratings are based on net installed radiation of sufficient quantity for the requirements of the building and nothing needs to be added for normal piping and pick-up. Ratings are based on a piping and pick-up allowance of 1.15. An additional allowance should be made for unusual piping and pick-up loads.
- (3) GWC boilers must be vented directly to the outside.

### **DIMENSIONS**



## **EQUIPMENT**

- Factory tested
- · Cast iron sections with built-in air separator
- Stainless steel secondary heat exchanger with air separator
- · Blower assembly with observation port.
- Electrical junction box
- 30 PSI ASME relief valve
- Hot surface ignition system
- System circulator\*
- Built-in-bypass circulator system with sensor for temperature control\*

- Negative regulation gas valve
- Gas/air orifice plate for natural gas (separate plate provided with unit for conversion to propane)

#### **OPTIONAL**:

- · Concentric vent kit
- · High altitude kit
- · Condensation neutralizer kit

\*Circulator supplied with boiler cannot be removed and cannot be used as a zone circulator in multiple zone systems.

















In the interest of continual improvement in product and performance, Williamson reserves the right to change specifications without notice.



8201 West Calumet Road . Milwaukee, WI 53223 www.williamson-thermoflo.com